



LEGEND	
-3	Feet of Cut
+1	Feet of Fill

**Total Site Earthwork**  
 Cut = 48684 yards  
 Fill = 27176 yards  
 Net = 21507 yards CUT

**Note:**  
 It is anticipated that the proposed grades will be adjusted approximately 7 to 8 inches on the Final Project Plans so that there will be balanced earthwork with no import or export of material.

**Figure 7-6: Earthwork Map**  
 Salem Hunt  
 Town of North Salem, Westchester, New York  
 Source: Insite Engineering, Surveying & Landscape Architecture, P.C., 8/31/07  
 Scale: 1" = 160'